

(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042. Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

SUMMARY OF TEST REPORT

TEST REPORT NO: ATCC2/16112909

DATE: 20/12/2016

(Number of Pages in Test Report: Page No. 1 to36)

TEST FORMAT AS PER A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013/ A2: 2013 for IEC 60950-1: 2005 + A1: 2009

1. Name of the Manufacturer: Shenzhen Cloudpoint Technology Co., Ltd

2. Product: Zero Client (Automatic Data Processing Machine)

3. Model: Lead model: S100

Series model: S100W, V1, V1W, A1, A1W, I1, I1W

4. Model differences provided (if applicable): Yes/No

5. Model differences verified as per DEITY Guidelines for series formulation; Yes/No

6. Test Results: Refer below

PARTA: GENERAL

SL. NO.	TEST REQUIREMENT	TEST CODE	CLAUSE	VERDICT
- 1	Components	EL 2100	1.5	p
2.	Markings and instructions	EL 2101	1.7	D

PART B:PROTECTION FROM HAZARDS

SL. NO.	TEST REQUIREMENT	TEST CODE	CLAUSE	VERDICT
1	SELV circuits	EL 2102	223	P
2	Provisions for earthing and bonding	EL 2103	2.6.2	N/A
3.	Overcurrent and earth fault protection in primary circuits		2.7.1	P
4.	Electrical Insulation	EL 2105	2.9	P
5,	Clearances, creepage distance and distances through insulation	EL 2106	2.10	N/A

Page 1 of 3





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

TEST REPORT NO: ATCC2/16112909

DATE: 20/12/2016

PART C: WIRING, CONNECTIONS AND PHYSICAL REQUIREMENTS

SL. NO	TEST REQUIREMENT	TEST CODE	CLAUSE	VERDICT
1.	Connection to a mains supply	EL 2107	3.2.5	N/A
2	Disconnections from the main supply	EL 2108	3.4.11	N/A
3.	Stability	EL 2109	4.1	N/A
4,	Design and construction	EL 2110	4.3	N/A
5.	Protection against hazardous moving parts	EL 2111	4.4.5.2	N/A
6.	Resistance to fire	EL 2122	4.7.3.4	p

PART D: ELECTRICAL REQUIREMENTS AND SIMULATED ABNORMAL CONDITIONS

SL. NO.	TEST REQUIREMENT	TEST CODE	CLAUSE	VERDICT
1.	Electric strength	EL 2113	5.2.2	N/A

PART E:CONNECTION TO TELECOM AND CABLE DISTRIBUTION SYSTEM

SL. NO.	TEST REQUIREMENT	TEST CODE	CLAUSE	VERDICT
1.	Protection of equipment users from overvoltages on telecommunication networks	EL 2114	6.2.2	N/A
2.	Connection to cable distribution systems	EL 2115	7.4.3	N/A

GENERAL INFORMATION:

 The conformity certificates of critical components are verified to ensure complete testing of apparatus under test and details regarding harmonized IEC standards (where IEC standards are not available) are also provided in the list of critical components.

Page 2 of 3



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

TEST REPORT NO: ATCC2/16112909

DATE: 20/12/2016

CONCLUSION:

- Sample meets all relevant requirements of A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013/ A2 : 2013 for IEC 60950-1: 2005 + A1: 2009
- 2.) Sample fails to meet the following test requirements.
- 3.) I, hereby undertake that the verdict stated in the test reports for all the test matches with the test results. The sample meets all relevant requirements A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013/A2: 2013 for IEC 60950-1: 2005 + A1: 2009/ does not meet the requirements If any deviation found, suitable punitive action may be taken by BIS.

Date: 20/12/2016

(Signature of Authorized person with Stamp)

YAD RAM
Technical Manager



Page 3 of 3



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Test Report No.: ATCC2/16112909 Page 1 of 36 Issue Date: 20/12/2016 Shenzhen Cloudpoint Technology Co., Ltd Manufacturer: Room 709, the Gold Hotel, Shennan East Rd., Luohu District, Shenzhen Zero Client (Automatic Data Processing Machine) Test item: Lead model: S100 Identification: Serial No.:Nil Series model: S100W, V1, V1W, A1, A1W, I1, I1W 16112909 Receipt/job No.: 29/11/2016 Date of receipt: Testing laboratory and its Amit Test And Calibration Centre (Unit 2) address: Kh.no. 45/14,17 & 45/6 & 7 Village Prahaladpur Bangar, Near Kali Mata Mandir Delhi-110042 Test specification: A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013 / A2: 2013 for IEC 60950-1: 2005 + A1: 2009 Test Result. The test item passed / failed the test specification(s). Other Aspects: This test report consists of 36 pages This test report relates to the test sample submitted and list of documents attached.

Tested by:	Approved by / Authorized Signatory:	Issued by:
10	7lan	Ket
Testing Engineer: Kapil Dhaka	Technical Manager: Yad Ram	Quality Manager: Rajiv Jadon
Date: 20/12/2016	Date: 20/12/2016	Date: 20/12/2016





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website : www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated:

20/12/2016

A2: 2013 for IEC 60950-1: 2005 + A1: 2009

Page 2 of 36

TEST REPORT

A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013/ A2: 2013 for IEC 60950-1: 2005 + A1: 2009 Information technology equipment - Safety -

Part 1: General requirements

"Automatic Data Processing Machine"

ATCC2/16112909 Date of issue 20/12/2016 Total number of pages..... Testing Laboratory Amit Test And Calibration Centre (Unit 2) Address Kh.no. 45/14,17 & 45/6 & 7 Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Manufacturer's name Shenzhen Cloudpoint Technology Co., Ltd Address Room 709, the Gold Hotel, Shennan East Rd., Luchu District, Shenzhen Test specification: Standard A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013 / A2: 2013 for IEC 60950-1: 2005 + A1: 2009 Test procedure Compliance Report Non-standard test method..... N/A Test Report Form No..... BIS_IT/ADP IS13252 A2 V1.0 Test Report Form(s) Originator Bureau of Indian Standards Master TRF 26/10/2015 Test item description Zero Client (Automatic Data Processing Machine) Trade Mark √cloudpoint Model/Type reference.....

Tested by:	Approved by / Authorized Signatory:	Issued by:
do-	7 au	Roj
Testing Engineer: Kapil Dhaka	Technical Manager: Yad Ram	Quality Manager: Rajiv Jadon
Date: 20/12/2016	Date: 20/12/2016	Date: 20/12/2016

Series model: S100W, V1, V1W, A1, A1W, I1, I1W

Please refer to Table - List of Attachments at Page No.06

Lead model: \$100

5.0V ____ 2.0A

Ratings

Other Documents submitted.....



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

Page 3 of 36

TEST REPORT

Report No. ATCC2/16112909 A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated: 20/12/2016 A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Test Code	Description	Measurement/ testing	Total No. of tests	Total no. of applicable tests/ Req.	No. of tests/ Req. passed	Page No.
EL 2100	General Requirements	Components (Cl.1.5)	08	07	07	09
EL 2101	Marking Requirements	Marking & instructions (Cl.1.7)	09	07	07	10
EL 2102	Electrical safety	SELV Circuits (Cl.2.2)	01	01	01	11
EL 2103	Electrical safety	Provisions for earthing and bonding (Cl.2.6)	02	00	N/A	12
EL 2104	Electrical safety	Overcurrent and earth fault protection in primary circuits (Cl.2.7)	01	01	01	13
EL 2105	Electrical safety	Electrical Insulation (CI.2.9)	03	03	03	14
EL 2106	Electrical safety	Clearances, Creepage distances and distances through insulation (Cl.2.10)	02	00	N/A	15
EL 2107	Wiring	Connection to a main supply (Cl.3.2)	01	00	N/A	16
EL 2108	Wiring	Disconnection for the main supply (Cl.3.4)	01	00	N/A	17
EL 2109	Mechanical properties	Stability (Cl.4.1)	04	00	N/A	18
EL 2110	Mechanical properties	Design and construction (Cl.4.3)	06	00	N/A	19
EL 2111	Mechanical properties	Protection against hazardous moving parts (Cl.4.4)	02	00	N/A	20
EL 2112	Fire Safety	Resistance to fire (Cl.4.7)	02	02	02	21
EL 2113	Insulating properties	Electric Strength (Cl.5.2)	01	00	N/A	22
EL 2114	Communicating connection	Protection of equipment users from overvoltages on telecommunication networks (Cl.6.2)	01	00	N/A	23
EL 2115	Connection to cable distribution	Connection to cable distribution systems	01	TEST .	N/A	24

TRF No. BIS_IT/ADP_IS13252_A2_V1.0



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909 A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 / Page 4 of 36

Dated: 20/12/2016 A2: 2013 for IEC 60950-1: 2005 + A1: 2009

	systems	(Cl.7)				
EL 2116	Insulating properties	Motor tests under abnormal conditions (Annex B)	02	00	N/A	25
EL 2117	Insulating properties	Measuring Instruments For Touch-Current Tests (Annex D)	01	00	N/A	26
El 2118	Electrical Safety	Measurement Of Clearances And Creepage Distances(Annex F)	01	01	01	27
EL 2119	General Requirements	Normative References(Annex P)	01	00	N/A	28
EL 2120	General Requirements	Voltage dependent resistors (VDRs) (Annex Q)	03	03	03	29
EL 2121	Wiring	Insulated Winding Wires For Use Without Interleaved Insulation(Annex U)	01	00	N/A	30
EL 2122	Radiation safety	Ultraviolet Light Conditioning Test(Annex Y)	02	00	N/A	31
EL 2123	Electrical Safety	Evaluation of integrated circuit (IC) current limiters (Annex CC)	05	00	N/A	32

Certificate: It is certified that the above tests were performed and found to be passing/Failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 5 of 36

Dated:

20/12/2016

A2: 2013 for IEC 60950-1: 2005 + A1: 2009

Copy of marking plate:



Making of lead model



Marking of switching adapter





FC (NOM Made in PRC www.vcloudpoint.com











Marking of series models







(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909 A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 6 of 36

Dated: 20/12/2016 A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Table - L	st of A	ttachments
-----------	---------	------------

Attachment No.	Attachment Description	No. of pages in Attachment
Attachment – 1	Plug dimension	35
Attachment – 1	Photo Document	36

General remarks:

The test results presented in this report relate only to the object tested.

This report shall not be reproduced, except in full, without the written approval of the Issuing testing laboratory.

Possible test case verdicts:

- test object does not meet the requirement F (Fail)

Testing...

Date(s) of performance of tests From 06/12/2016 to 19/12/2016

Laboratory conditions

Ambient Humidity 50±5 % RH





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909	A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /	Page 7 of 36
Dated: 20/12/2016	A2 : 2013 for IEC 60950-1: 2005 + A1: 2009	

Test item particulars	Zero Client (Automatic Data Processing Machine)
Equipment mobility	□ movable □ hand-held □ transportable □ stationary □ for building-in □ direct plug-in
Connection to the mains	☐ pluggable equipment ☐ type A ☐ type B ☐ permanent connection ☐ detachable power supply cord ☐ non-detachable power supply cord ☑ not directly connected to the mains
Operating condition	□ continuous □ rated operating / resting time:
Access location	operator accessible restricted access location
Over voltage category (OVC)	☐ OVC I ☐ OVC II ☐ OVC III ☐ OVC IV ☑ other: SELV
Mains supply tolerance (%) or absolute mains supply values	N/A
Class of equipment	☐ Class II ☐ Class II ☐ Class III ☐ Not classified
Considered current rating protective device as a part of the building installation (A)	N/A
Pollution degree (PD)	□PD1⊠PD2 □PD3
IP protection class	
Altitude during operation (m)	Up to 2000
Altitude of test laboratory (m)	< 1000
Mass of equipment (kg)	0.109 Kg.
Abbreviations that may be used throughout this to	est report:
PE/PB protective earth/protective bonding	Pri: primary
CB circuit breaker	sec secondary
(SW)PS (switching) power supply	gnd ground
HV high voltage	I/Oinput/output
PCB printed circuit (wiring) board	ii installation instruction
TIW: triple insulated wire	PSU Power Supply Unit
B/I built-in application (compliance shall	be guarantee in host equipment)
F/B/S/R: Functional/Basic/Supplementary/Reinforced	





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909 A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 8 of 36

Dated: 20/12/2016 A2 : 2013 for IEC 60950-1; 2005 + A1: 2009

General product information:

1) Application details / Description of the product:

The equipment under test is "Zero Client (Automatic Data Processing Machine)" of model: "S100".

Certified Switching adapter with input: 90-270~, 50/60Hz, 0.5A MAX and Output: 5.0V = = 2.0A

Max. Specified ambient temperature (°C)...... 25 °C

Model No. tested with-in the family series .: \$100

3) Options:

The equipment was tested without any optional accessory installed. Hence, this report does not cover parameters that are influenced by the installation of optional accessory that might affect safety in the meaning of this standard.





Dated:

AMIT TEST AND CALIBRATION CENTRE

(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

20/12/2016

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to General Requirements

EL 2100 A2- V1.0

Page 9 of 36

CL No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
1.5	Components*	EL 2100-00	Verification of approvals with due correlation between the components used and the approval certificates submitted (Please see the table 1.5.1)	P
1.5.1	General:		See below	Р
	Components shall be complying with IEC 60950-1 or relevant component standard.	EL 2100-01	Component certified with relevant component standard	P
	Components and subassemblies approved for IEC 62368-1 can be considered as complying with this standard	EL 2100-02	See above	N/A
1.5.2	Evaluation and testing of components	EL 2100-03	Component certified to IEC standard and/or their harmonized standards are used within their ratings (See Table 1.5.1)	Р
1.5.6	Capacitors bridging insulation *	EL 2100-04	Certified adapter used	Р
1.5.7.2	Resistor bridging double or reinforced insulation between a c mains and other circuits	EL 2100-05	See above cl. no. 1.5.6	Р
5.9.2	Protection of VDRs	EL 2100-06	Certified adapter used	P
.5.9.4	Bridging of basic insulation by a VDR*	EL 2100-07	See above cl.no 1.5.9.2	P

*Total number of Requirements to be observed / inspected	= 03
Total No of applicable Requirement	= 03
No of Requirements for which the sample passed	= 03
Total number of tests to be conducted	= 05
Total No of applicable Tests	= 04
No. of tests for which the sample passed	= 04

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)

YAD RAM
Technical Manager

CALIBA ASITE OF ABOUT THE BRIDGE PUR TO BE BRIDGE PUR TO

TRF No. BIS_IT/ADP_IS13252_A2_V1.0



Dated:

AMIT TEST AND CALIBRATION CENTRE

(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1 : 2013 /

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Marking Requirements

20/12/2016

EL 2101_A2-V1.0

Page 10 of 36

Cl. No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
1.7	Marking and instructions*	EL 2101-00	See below	verdica
1.7.1.1	Power rating markings*	EL 2101-01	See below	P
	Rated voltage(s) or voltage ranges(s) (V)*.	EL 2101-02	5.0Vdc	P
	Multiple mains supply connections*	EL 2101-03	No multiple mains supply	N/A
	Symbol for nature of supply, for d.c. only*:	EL 2101-04	Marked on marking plate	P
	Rated frequency or rated frequency range (Hz) *:	EL 2101-05	DC supply	N/A
	Rated current (mA or A)*:	EL 2101-06	2.0A	P
1.7.1.2	Identification markings*	EL 2101-07	Provided	P
1.7.1.3	Use of graphical symbols*	EL 2101-08	Symbols used	P

*Total number of Requirements to be observed / inspected = 09

Total No of applicable Requirement = 07

No of Requirements for which the sample passed = 07

Total number of tests to be conducted = 00

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated:

20/12/2016

A2: 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Electrical Safety

EL 2102 A2-V1.0

Page 11 of 36

CI NI-	Total Property Commence of the	and the second second second second		
CI. NO.	Test / Requirement name	Test Code	Test result/ observation	Verdict
2.2.3	Voltage under fault condition	EL 2102-00	Certified adapter used	The state of the s
			ocimico adapter used	P

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 01

No of tests for which the sample passed = 01

Certificate: It is certified that the above tests were performed and found to be passing/failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1 : 2013 /

Page 12 of 36

Dated

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Electrical Safety

EL 2103 A2- V1.0

Cl. No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
2.6.2	Functional earthing: The Functional earthing either separated from hazardous voltages by double- or reinforced insulation or safely connected to Protective Bonding Conductor.*	EL 2103-00	Class III equipment powered by certified adapter used	N/A
	Use of symbol for functional earthing *	EL 2103-01		N/A

*Total number of Requirements to be observed / inspected = 02

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 00

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

7 Jan

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

Tests relating to Electrical Safety

A2 : 2015 for IS 13252 (Part 1): 2010 + A1 : 2013 /

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

EL 2104 A2- V1 0

Page 13 of 36

CI. No.	Test / Requirement name	Test Code	Test result/ observation	L 2104_A2- V1
2.7.1	Basic requirements:		THE RESIDENCE AND LAND AND THE PARTY OF THE	Verdict
5031	The built-in device fuse provides overcurrent protection. OR The equipment is protected by the built-in circuit breaker.*	EL 2104-00	Certified adapter used	P

*Total number of Requirements to be observed / inspected = 01

Total No of applicable Requirement = 01

No of Requirements for which the sample passed = 01

Total number of tests to be conducted = 00

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 14 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Electrical Safety

EL 2105 A2- V1.0

CI. No.	Test / Requirement name	Tool Code		MZ- V 1.1
THE REAL PROPERTY.	1792 HILL O'STRING ON GENERAL AND AND SHEET OF SHEET	Test Code	Test result/ observation	Verdict
2.9	Electrical insulation*	EL 2105-00		P
2.9.1	Properties of insulating materials*	EL 2105-01	Natural rubber, material containing asbestos and hygroscopic material are not used	P
2.9.2	Humidity conditioning	EL 2105-02	See below	D
	Relative Humidity: 93 ±3 %, Temperature: t at 40 ± 2°C Duration: 120 hours		Relative Humidity: 93%Rh, Temperature: t at 40°C Duration: 120 hours	P

*Total number of Requirements to be observed / inspected = 02

Total No of applicable Requirement = 02

No of Requirements for which the sample passed = 02

Total number of tests to be conducted = 01

Total No of applicable Tests = 01

No. of tests for which the sample passed = 01

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 15 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Electrical Safety

EL 2106_A2-V1.0

CI. No.	Test / Dentito	A ANNUAL PROPERTY AND ADDRESS.	I Company	EE 2100_A2- V1.0
STATE OF THE PARTY AND	Test / Requirement name	Test Code	Test result/ observation	Verdict
2.10.10	Test for Pollution Degree 1 environment and for insulating compound	EL 2106-00	Pollution degree 2	N/A
2.10.11	Tests for semiconductor devices and cemented joints	EL 2106-01		N/A

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 02

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909 A2: 2015 for IS 13252 (Part 1): 2010 + A1: 2013 / Page 16 of 36

Dated: 20/12/2016 A2: 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Wiring

EL 2107 A2- V1.0

CL No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
3.2.5	Power supply cords		Power supply cord not used	N/A
3.2.5.1	3.2.5.1 AC power supply cords	EL 2107-00	See above cl. no. 3.2.5	N/A
	Rated current (A), cross- sectional area (mm²), AWG	1-11	See above cl. no. 3.2.5	N/A

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate. It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

Tests relating to Wiring

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

FI 2108 A2 V4 0

Page 17 of 36

				EL 2108_A2- V1.0
Cl. No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
3.4.11	Multiple power sources*	EL 2108-00	The state of the s	1000
	THE PROPERTY OF THE PARTY OF TH			N/A

"Total number of Requirements to be observed / inspected = 01

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 00

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)

YAD RAM





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 18 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Mechanical Properties

EL 2109 A2-V1.0

Cl. No.	Test / Requirement name	Test Code	Test result/ observation	09_A2- V1.0
4.1	Stability	EL 2109-00	TARREST MANAGEMENT AND ADDRESS OF THE PARTY	Verdict
	220002200		Mass of equipment is 0.109Kg	N/A
	a) A unit having a mass of 7 kg or more shall not fall over when tilted to an angle of 10° from its normal upright position. Alternatively, the unit is placed in its intended position of use on a plane, inclined at an angle of 10° to the horizontal, and then rotated slowly through an angle of 360° about its normal vertical axis.	EL 2109-01	Mass less than 7 Kg.	N/A
	b) A floor-standing unit having a mass of 25 kg or more shall not fall over when a force equal to 20 % of the weight of the unit, but not more than 250 N, is applied in any direction except upwards, at a height not exceeding 2 m from the floor.	EL 2109-02	Not a floor standing equipment	N/A
	c) A floor-standing unit shall not fall over when a constant downward force of 800 N is applied at the point of maximum moment to any horizontal surface of at least 125 mm by at least 200 mm, at a height up to 1 m from the floor	EL 2109-03	Not a floor standing equipment	N/A

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 04

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)

YAD RAM

Technical Manager

CALIBRA 45/14

O Prohalad Pur

Dath-110042

TO

Dath-110042

TRF No. BIS_IT/ADP_IS13252 A2 V1.0



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 19 of 36

Dated:

20/12/2016

A2: 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Mechanical Properties

EL 2110 A2- V1.0

CI. No.	Test / Description	THE PARTY NAMED IN		10_A2- V1.0
TO SERVICE STATE OF THE SERVIC	Test / Requirement name	Test Code	Test result/ observation	Verdict
4.3.8	Batteries	1 - 1 11	Battery not used	N/A
	a) Overcharging of a rechargeable battery	EL 2110-00	See above 4.3.8	N/A
	b) Unintentional charging of a non-rechargeable battery	EL 2110-01	See above 4.3.8	N/A
	c) Reverse charging of a rechargeable battery	EL 2110-02	See above 4.3.8	N/A
	d) Excessive discharging rate for any battery	EL 2110-03	See above 4.3.8	N/A
	e) Electric strength as per Cl.5.3.9.2	EL 2110-04	See above 4.3.8	N/A
4.3.13.5.2	Light emitting diodes (LED's)	EL 2110-05	Low power LED used as functional indicators	N/A

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 06

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 20 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Mechanical Properties

EL 2111 A2- V1.0

CI No	CL No. Test / Requirement name			EL 2111_M2- VI	
CL IND.	Test / Requirement name	Test Code	Test result/ observation	Verdict	
4.4.5.2	Protection for users*	EL 2111-00	No moving parts	N/A	
	Use of symbol or warning*	EL 2111-01			
		- COOL-14 Feb.		N/A	

*Total number of Requirements to be observed / inspected = 02

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 00

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 2015 for IS 13252 (Part 1): 2010 + A1 2013 /

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Fire Safety

EL 2112 A2- V1.0

Page 21 of 36

CI. No.	Test / Requirement name	Toot Code		2_A2- V1.
Control of the Asset	THE COMP STORY OF STREET, HERE SELECT	Test Code	Test result/ observation	Verdict
4.7.3.4	Materials for components and other parts inside fire enclosures		Certified material used (See table 1.5.1)	Р
	 a) Inside FIRE ENCLOSURES, materials for components and other parts shall comply with one of the following: 	EL 2112-00	Components are mounted on V-0 class material	P
	- be of V-2 CLASS MATERIAL or			
	HF-2 CLASS FOAMED MATERIAL: or			
	pass the flammability test described in Clause A.2; or	- Apr 3 2		
	meet the flammability requirements of a relevant IEC component standard that includes such requirements.			
	Requirements for voltage dependent resistors (VDR's) are in Annex Q.*	EL 2112-01	Certifies adapter used	P

*Total number of Requirements to be observed / inspected = 01

Total No of applicable Requirement = 01

No of Requirements for which the sample passed = 01

Total number of tests to be conducted = 01

Total No of applicable Tests = 01

No. of tests for which the sample passed = 01

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

l Cim

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Page 22 of 36

Tests relating to Insulating Properties

CI. No.	Test / Requirement name	Test Code	Test result/ observation	2113_A2- V1.0
5.2.2	Test procedure	11.000	The state of the s	Verdict
	The second secon		Class III equipment	N/A
	a) The test voltages for electric strength for the appropriate grade of insulation [FUNCTIONAL INSULATION if required by 5.3.4 b), BASIC INSULATION, SUPPLEMENTARY INSULATION or REINFORCED INSULATION] are as specified in either:	EL 2113-00	See above	N/A
	Table 5B using the PEAK WORKING VOLTAGE (U), as determined in 2.10.2, or			
	Table 5C using the REQUIRED WITHSTAND VOLTAGE, as determined in G.4.			

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website : www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 2015 for IS 13252 (Part 1): 2010 + A1 2013 /

Dated:

20/12/2016

Tests relating to Communicating Connection

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Page 23 of 36

CI NI-	The latest terminal t	A STATE OF THE PARTY OF THE PAR	EL 211	4_A2- V1.
CI. No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
6.2.2	Electric strength test procedure		Equipment is not for connection to telecommunication network	THE PERSON NAMED IN

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the

requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1 2013 /

Page 24 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Connection to cable distribution system

EL 2115_A2-V1.0

Cl. No.	Test / Requirement name	Test Code	Test result/ observation	Verdict
7.4.3	Impulse test	EL 2115-00	The second second	
				N/A

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate. It is certified that the above tests were performed and found to be passing/ falling in the requirement tested.

(Approving Authority)

YAD RAM





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

42 2040 5 150 2000

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Insulation Properties

EL 2116 A2-V1.0

Page 25 of 36

Cl. No.	Test / Describe assets assets	and the control of the control	I was a second s		
	Test / Requirement name	Test Code	Test result/ observation	Verdict	
B.7.2	Test procedure	EL 2116-01	Description of the second	N/A	
B.7.3	Alternative test procedure	EL 2116-02		N/A	
				IVA	

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests ≈ 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

MI TANA

(Approving Authority)

YAD RAM





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website : www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Insulation Properties

EL 2117_A2- V1.0

Page 26 of 36

Cl. No. Test / Requirement name		Committee of the Control of the Cont			
CI. IVO.	Test / Requirement name	Test Code	Test result/ observation	Verdict	
D.1	Measuring instrument	EL 2117-00	Class III equipment	N/A	
117				1905	

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ falling in the requirement tested.

(Approving Authority)

YAD RAM





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website : www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 2015 for IS 13252 (Part 1): 2010 + A1 2013 /

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Page 27 of 36

Tests relating to Electrical Safety

CI. No.	Tool / Dan Bally 1	THE RESIDENCE OF	EL 2118_A	
CI. NO.	Test / Requirement name	Test Code	Test result/ observation	Verdict
F	ANNEX F, MEASUREMENT OF CLEARANCES AND CREEPAGE DISTANCES (see 2.10 and Annex G)	EL 2118-00	Certified adapter used	P

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 01

No. of tests for which the sample passed = 01.

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)

YAD RAM





Dated:

AMIT TEST AND CALIBRATION CENTRE

(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

20/12/2016

A2 2015 for IS 13252 (Part 1): 2010 + A1 2013 /

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to General Requirements

EL 2119 A2-V1.0

Page 28 of 36

CI. No	Test/ Describe course	The second secon	The same of the sa		
CI. IVO.	Test / Requirement name	Test Code	Test result/ observation	Verdict	
Р	Annex P, NORMATIVE REFERENCES	EL 2119-00	A STATE OF THE STA	N/A	

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

1/00

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to General Requirements

EL 2120 A2- V1.0

Page 29 of 36

Cl. No.	Test / Requirement name	490212W2007		0_A2- V1.(
COLUMN TO A	The state of the s	Test Code	Test result/ observation	Verdict
Q	ANNEX Q, Voltage dependent resistors (VDRs) (see 1.5.9.1)	EL 2120-00	Certified adapter used	P
	a) Preferred climatic categories		See above Q	P
	b) Maximum continuous voltage:		See above Q	P
	c) Combined pulse		See above Q	P
	d) Body of the VDR complies with V-1 CLASS MATERIAL: *	EL 2120-01	See above Q	P
	e) Needle flame test according to IEC 60695-11-5 [Note: This test is not required if VDR complies with V-1 CLASS MATERIAL]	EL 2120-02	See above Q	Р

*Total number of Requirements to be observed / inspected	= 01	
Total No of applicable Requirement	= 01	
No of Requirements for which the sample passed	= 01	
Total number of tests to be conducted	= 02	
Total No of applicable Tests	= 02	

Certificate: It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)

YAD RAM

No of tests for which the sample passed



= 02



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 2015 for IS 13252 (Part 1): 2010 + A1 2013 /

Page 30 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Wiring

EL 2121 A2- V1.0

Cl. No.	Test / Requirement name	Test Code	Test result/ observation	V2-1914
U	ANNEX U, INSULATED WINDING WIRES FOR USE WITHOUT INTERLEAVED INSULATION (see 2.10.5.4)	EL 2121-00		Verdict: N/A

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 01

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate. It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Dated: 20/12/2016 A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Radiation Safety

EL 2122 A2-V1.0

Page 31 of 36

Test / Paguiroment serve	t / Requirement name T- + 0 / F		
rest / Requirement name	Test Code	Test result/ observation	Verdict
ANNEX Y, ULTRAVIOLET LIGHT CONDITIONING TEST (see 4.3.13.3)	EL 2122-00	No ultraviolet light	N/A
Test apparatus	EL 2122-01	See above Y	N/A
	LIGHT CONDITIONING TEST (see 4.3.13.3)	ANNEX Y, ULTRAVIOLET LIGHT CONDITIONING TEST (see 4.3.13.3)	ANNEX Y, ULTRAVIOLET LIGHT CONDITIONING TEST (see 4.3.13.3) EL 2122-00 No ultraviolet light

*Total number of Requirements to be observed / inspected = 00

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 02

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate. It is certified that the above tests were performed and found to be passing/ falling in the requirement tested.

lain

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 32 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Tests relating to Electrical Safety

EL 2123 A2- V1.0

Requirement name ted circuit (IC) current	Test Code	Test result/ observation No integrated circuit (IC) as current limiters used	Verdict N/A
*		No integrated circuit (IC) as current	N/A
		inniters used	
ogram 1	EL 2123-00	See above CC.1	N/A
ogram 2	EL 2123-01	See above CC 1	N/A
ogram 3	EL 2123-02	TO BUT HOLD CORE OF THE PARTY O	N/A
ance	EL 2123-03	N. C.	N/A
	ogram 2 ogram 3	ogram 2 EL 2123-01 ogram 3 EL 2123-02	ogram 2 EL 2123-01 See above CC 1 ogram 3 EL 2123-02 See above CC 1

*Total number of Requirements to be observed / inspected = 01

Total No of applicable Requirement = 00

No of Requirements for which the sample passed = N/A

Total number of tests to be conducted = 04

Total No of applicable Tests = 00

No. of tests for which the sample passed = N/A

Certificate. It is certified that the above tests were performed and found to be passing/ failing in the requirement tested.

(Approving Authority)





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 2015 for IS 13252 (Part 1) 2010 + A1 2013 /

Page 33 of 36

Dated: 20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

1.5.1	TAE	BLE: List of components						
Object/part	no.	Manufacturer/ trademark	Type/model	Technical data	Standard	Mark(s) of conformity		
Switching Adapter		HENZHEN SOY TECHNOLOGY CO.LTD.	SOY-0500200IN	Input: 90-270V~, 50-60Hz, 0.2A MAX Output: 5.0Vdc, 2.0A	IS 13252(Part- 1): 2010	BIS R-41020370		
PCB		DONGGUAN CITY XINRAN ELECTRONIC CO LTD	XR-F003	130°C, V-0	UL 796 UL E33 (No equivalent to IEC standard)			
Enclosure		ZHEN JIANG CHI MEI CHEMICAL CO LTD	D-1200 ·	ABS, HB or above	UL 94 (Equivalent to IEC 60695-11- 10)	UL E194560		

Supplementary information:



Evidences provided by the manufacturer for the listed components are verified by us and the evidences are conforming to the requirements of the relevant standard.



(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

TEST REPORT

Report No	ATCC2/16112909	A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /	Page 34 of 36
Dated:	*****	A2 : 2013 for IEC 60950-1: 2005 + A1: 2009	1 age 34 01 30

2.2.3	TABLE: SELV measure	ment (under fault conditions)	р	
Location		Voltage (max.) (V)	Comments	
		-		
Supple	mentary information: Cert	ified adapter used		

4.3.8	TABLE	Batteries							1	
The tests	of 4.3.8 are	applicable	only when ap	propriate i	nattery I				N/A	
data is not	available								N/A	
Is it possib	le to install	the battery	in a reverse	polarity po	sition?				N/A	
		echargeabl				Rechargea	ble batteri	es	1 1400	
DOS OFFI	Discharging Un-			Cha	Charging		arging	Reversed	ed charging	
	Meas: current	Manuf. Specs.	charging	Meas.	Manuf. Specs.	Meas. current	Manuf. Specs.	Meas	Manuf.	
Max. current during normal condition	AND OLD					94		- Culteria	Specs	
Max. current during fault condition					100 TALL				-	
Test results									Maniform	
- Chemical									Verdict	
	of the batte						_			
 Emission (of flame or	expulsion (of molten meta	al						
- Electric str	ength tests	s of equipm	ent after com	pletion of to	ests		-			
Supplement	tary informa	ation: Batt	ery not used	production of	0010				-	

5.2	TABLE: Electric strength tests, impuls	igth tests, impulse tests and voltage surge tests					
	Test voltage applied between,	Voltage shape (AC, DC, impulse, surge)	Test voltage (V)	Breakdown Yes / No			
Function	nal:						
Basic / s	supplementary:						
		-					
Reinforc	ed:						
			-				
Supplen	nentary information : Class III equipment						





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website: www.atncc.in

Page 35 of 36

TEST REPORT

Report No. ATCC2/16112909

20/12/2016


A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

Attachment No. 1

Dated:

India plug test report



Tune of Diver Ton	A SAME OF THE SAME	Total Control	Plug Dimension	IS A COLUMN TO A STATE OF THE S		CONTRACTOR OF
Type of Plug: Two	pin [X] Three	e pin[]	CONTRACT DESCRIPTION		THE CHARLES	STEAT I
Reference points		HI TO SEE THE SE	Ratin	gs	THE SHOPPING	CATTER OF THE
	2.5A[X]		10A	11	16A[]	
	Limits	Measured	Limits	Measured	Limits	Measured
Α	-		22.05-22.35	-	28.45-28.75	AND SAFETY OF
В	18.95-19.25	18.96	18.95-19.25		25.25-25.55	
С		-	7.01-7.085	-	8.66-8.735	*
D	5.03-5.105	5.06	5.03-5.105		7.01-7.085	-
E	15.77-16.94	16,27	15.77-16.94	-	20.47-21.64	
F			20.47-21.64		28.47-29.64	
G	7.94 (min.)	10.54	7.94 (min.)	-	9.52 (min.)	





(NABL ACCREDITED LABORATORY)

Kh.No. 45/14,17 & 45/6 & 7, Village Prahaladpur Bangar, Near Kali Mata Mandir, Delhi-110042 Ph.: 011-65651602, 65651603 Email: amittestcc2@gmail.com Website : www.atncc.in

TEST REPORT

Report No. ATCC2/16112909

A2 : 2015 for IS 13252 (Part 1): 2010 + A1: 2013 /

Page 36 of 36

Dated:

20/12/2016

A2 : 2013 for IEC 60950-1: 2005 + A1: 2009

PHOTOGRAPHS




TOP VIEW 1




BOTTOM VIEW




PORT VIEW



SWITCHING ADAPTER



PCB VIEW 1



PCB VIEW 2

"END OF TEST REPORT"

